







Pipeline Commissioning



- What is Commissioning?
- Why Commissioning is Important?
- What are the Commissioning Phases?
- Why Commissioning with BRASS?
- BRASS Commissioning cases



What is Commissioning?



What is Commissioning?

- Asset commissioning is the process of testing all systems and components of an asset (such as a facility, equipment, or system) to ensure compliance of the engineering design, construction/assembly and testing in accordance to the operational requirements of the owner/client, suppliers and technical standards.
- This process is crucial to establish a base information and ensure that the system meets the required capacities, safely and efficiently prior to the commercial operation.



Why Commissioning is Important?



Why commissioning is important?

Operational Efficiency:

• Proper commissioning ensures that all systems are optimized, minimizing failures and interruptions during operation.

Safety:

 Verification of interlocks and protective devices reduces potential operational risks, ensuring a safe environment for equipment and workers.

Reliability:

• Endurance testing of the equipment ensures a failsafe operation and prolongs the lifespan of the pipeline system.

Resource Savings:

 Optimizing controls settings ensures a highly efficient operation that reduces losses and wastage during large-scale production.

Why commission your asset?





Ensure equipment functionality.

- Equipment alignment
- Vibration Testing
- Gear Box Temperature Testing
- Ensures functionality of bearings, shafts and motorpump couplings

Why commission your asset?

BRASS

Identify assembly failures that impact asset performance.

- Inverted restriction orifice assembly
- Cracked ceramic chokes during assembly
- Verification of correct choke diameters and arrangement.




Why commission your asset?



Analyzing operation results

- LDS visualization
- Adjust operational parameters






What are the Commissioning Phases?




What Are the Commissioning Phases?





What Are the Commissioning Phases?







Confirmation of the correct assembly of the installations according to the project, specifications, and applicable standards:

- Visual Inspection
- Hydrostatic Test
- Continuity Test
- Insulation Test
- Equipment Lubrication
- Line Cleaning
- Alignment
- No-load tests

These are NOT IN SCOPE of Commissioning



Mechanical Completion

The EPC team will perform the validation of the mechanical completion protocols, and the results are presented in a report.


- Completion of Inspection Protocols/Records;
- Elaboration of the Punch List;
- Resolution of all Type A pending issues, allowing the issuance of a Punch List only with remaining Type B and C pending issues.
 - Type A: Preventive endangers the system, people, or the environment.
 - Type B and Type C: Non-preventive can be resolved during or by the end of commissioning.

These are NOT IN SCOPE of Commissioning.




Mechanical Completion

Custody Transfer Assembler/EPC to Commissioning:





What Are the Commissioning Phases?





Commissioning Planning

Main Activities (minimal requirements)

- Formation of groups and definition of roles and responsibilities;
- Organizational chart;
- Activity schedule or timeline;
- Development of Test Procedures, Protocols and Test Forms;
- Communication Plan and Lockout Procedure;
- Health, Safety and Environment Requirements (HSER);
- Others

Commissioning Planning





FIQUE ATENTO!

- SE VOCÉ ESTÁ NAS DEPENDÊNCIAS DO CLIENTE OU EM PROPRIEDADE DE TERCEIROS, PARTICIPE DE TODOS OS TREINAMENTOS QUE LHE FOREM SOLICITADOS E SÓ REALIZE SUAS ATIVIDADES SE PREVIAMENTE AUTORIZADO;
- NÃO ENTRE EM PROPRIEDADE PRIVADA SEM A DEVIDA AUTORIZAÇÃO;
- C SEMPRE REQUISITAR DO CLIENTE A AUTORIZAÇÃO FORMAL PARA ENTRAR EM TERRENOS DE TERCEIROS;
- D QUANDO ACORDADO COM O CUENTE, MANTENHA A DEVIDA IDENTIFICAÇÃO DA BRASS NO CARRO E SEMPRE UTILIZE UNIFORME E CRACHÁ.

BRASS BRASIL

R. Paraíba, 1.122 – 7° & 8° Andar
Savassi – Belo Harizonte i MG

ATENÇÃO ACESSO

SOMENTE PESSOAL AUTORIZADO

RESTRITO





Commissioning Requirements (examples)

- Communication Plan
- Rules Applied to the worksite

ATENÇÃO

ACESSO RESTRITO



SOMENTE PESSOAL AUTORIZADO












Commissioning Requirements (examples)

 Guidelines for tagging and blocking




Commissioning Planning

Asset Separation in Systems and Subsystems





What Are the Commissioning Phases?






Pre-Commissioning

Also known as **Cold Functional Testing** - Ensure that equipment is properly installed and ready to begin commissioning with load;

- Verification of Mechanical Completion (Turn Over Package TOP);
- Verification of field instrumentation and wiring connection from local electrical rooms and site control room signal verification
- Manual Valve Stroke and limit switch settings;
- Verification of relief valve/rupture disc installation and settings.
- Verification of Hydrostatic test records and technical standards.
- Verification of Valve and Choke positions.
- Verification of the completeness and adequacy of the MMI display in control room.
- Verification of equipment calibration

The pre-commissioning tests and activities will be executed, planned, and controlled by the commissioning team








Ensure Quality

- Step-by-Step inspection
- Evaluation of cathodic protection along the pipeline








Ensure Quality

- Valve movement testing (manual mode)
- Limit Switch Settings



What Are the Commissioning Phases?





Also known as **Hot Functional Testing** - Dynamic Verification of the asset (all subsystems)

• Load Tests Part 1, on Water:

- Pipeline filling and pigging
- Pressure Test (Static & Dynamic)
- Flow Capacity Testing on Water
- Pump Curve and Capacity Verification
- Choke Verification
- Remote/Local Instrumentation and Controls Interlock verification
- Shutdown and Restart Sequence verification
- Establish baseline information for pipeline roughness
- Vibration tests


The execution of commissioning subsystem tests will be carried out by the commissioning team with support from the suppliers themselves.





System analysis (Water)

- Motor vibration tests
- Centrifugal charge pump









Ensure Quality

 PIG run to ensure pipeline is free from air




Load test - Pipeline





System analysis (Water)

- Operational data analysis
- Evaluation of the system as an overall
- Check station elevation using static head
- Determine pipeline roughness



System analysis (Water)

- Validation of Operation Manual
- Startup and Shutdown sequence procedure testing
- Determine adequacy of chokes




Tabela 17: Sequência de Partida do Sistema	tema AMMCO
--	------------

ITEM	OPERAÇÕES	ESTAÇÕES	OBSERVAÇÕES
1.0	Partida do rejeitoduto com polpa		
1.1	Posicionar a draga em uma profundidade para bombear polpa.	Draga	
1.2	Garantir que a válvula que direciona rejeito para SP- 16 esteja fechada	FV-26-212	A válvula FV-26-212 deverá ser mantida trancada fechada
1.3	Fazer jogo de válvulas para permitir que apenas a linha da draga AMMCO esteja bombeando para Saracá Oeste	FV-26-213 e FV-26-214	A válvula FV-26-214 deverá ser mantida trancada aberta, enquanto a válvula FV-26-213, mantida trancada fechada
1.4	Fazer o jogo de válvulas para direcionar o fluxo para os espigotes	FV-26-252 / FV-26-253 / FV-26-254 / FV-26-269 / FV-26-270 / FV-26-271 / FV-26-273 / FV-26-274	Abertura de válvula local
1.5	Abrir as válvulas dos espigotes selecionados.	SP-25/ SP- 24/ SP-23	Devem ser abertos, no mínimo, 4 espigotes
1.6	Abrir todas as válvulas de sucção e descarga das bombas.	Draga, EB1, EB2, EB3	
1.7	Certificar que a válvula de by-pass de cada bomba está fechada.	EB1, EB2, EB3	

1.7	Certificar que a válvula de by-pass de cada bomba está fechada.	EB1, EB2, EB3	
		Draga, EB1, EB2, EB3	








General performance

- Charge slurry pump
- Pump Curve Performance
- On project operating range



What Are the Commissioning Phases?





Startup Testing

Also known as **Acceptance Testing** - Dynamic Verification of the asset (all subsystems).

Load Tests Part 2, on Slurry:

- Adjustments on control parameter and choke settings if required (based on Water Testing results)
- Admittance of slurry (granulometry, rheology, others)
- Capacity or performance testing within the Operating Range
- Shutdown and Restart at different slurry concentration
- Slurry testing Laboratory activities
- Adjustments of parameters and procedures for operational optimization (Operational Manual);
- General monitoring of the operation and endurance Testing


The execution of commissioning subsystem tests will be carried out by the commissioning team with support from the suppliers themselves.






Assisted Operation

- Monitoring operation in control room through DCS.
- Monitoring operation through LDS monitor
- Slurry Lab Testing





What Are the Commissioning Phases?







Optional – Gradually increasing production to meet product/service required capacity.

Comercial centered phase.

- Strategies of Production increase;
- Understanding customer needs;
- Validating characteristics of the transported slurry;
- · Identifying bottlenecks and problems to achieve full production.

Training (Optional)

Module 1: Introduction - Basic Concepts

- Hydraulic Aspects:
 - Hydraulic concepts;
 - Bernoulli equation;
 - Pressure loss;
 - HGL (Hydraulic Grade Line);
 - Hydraulic transients
- Mechanical properties of slurry laboratory test;
- Types of Fluids;
- Minimum transport velocity.

Module 2: Pipeline Equipment

- General project description;
- Main pipeline equipment;
- Supervisory system and control room;
- LDS screen;
- Cathodic protection;
- Auxiliary peripheral systems



Module 3: Operation and Control Philosophy

- Operational Diagram;
- Process Control and Interlocks;
- Pipeline Operation Modes;
- Equipment Groups;
 - Start-Up and Shutdown Procedures;
 - Tank Switching;
 - Booster Pump Switching;
 - Main Pump Switching.

Module 4: Maintenance, Integrity, and Emergency Plan

- Main Maintenance Procedures:
 - Weir Charge Pumps
 - GEHO Pumps
 - Slurry Filters
- Integrity:
 - Cathodic Protection Control
 - Tube Potential Measurement
 - PIG Inspection
 - Defect Correction

Mineral Pipeline Emergency Plan



Why Commissioning with BRASS?



BRASS Pipeline Commissioning

Prepared Team:

• BRASS has a solid Commissioning and Startup team that has been kept intact with an experience of over 25 years.

Available Consultants:

 Direct connection with the project development team and BRASS engineering consultants;

Training:

• Training directed towards the operation and maintenance teams;

Knowledge and Performance:

 Performance analysis and problem diagnosis performed in the field by the hydraulics team during system commissioning.



BRASS Commissioning Cases



Gelado Pipeline – Paraopebas, PA (Brazil) – VALE









Gelado Pipeline - Main equipment

- Tanks with agitators 21,50m x 17,00m;
- 04 hoists of 10 tons and 01 gantry crane of 15 tons
- 04 Slurry distributors;
- 02 Weir 14/12 AH Centrifugal Slurry Pumps;
- 02 Slurry Filters;
- Dilution system with 01 tank;
- 02 KSB Centrifugal Water Pumps;
- 04 Positive Displacement Pumps GEHO TZPM-2000;
- 02 Hydraulic Units;






Gelado Pipeline – Main equipment

- 35 Ball Valves with hydraulic actuation diameters 20", 12", 4" and 3";
- 13 Electropneumatic Panels;
- 59 Knife Valves with pneumatic actuation 24", 20", 8", 6", 4" and 3" diameters;
- O1 Launcher and O1 receiver from PIG Vanasa;
- 6,4 km API 5L X70 Carbon Steel Pipeline,
 20"diameters;
- Cathodic protection system;
- Automation and Instrumentation: 09 Remote Units, Density Meters, Level Meters, Flow Meters and Pressure Transmitters.



Central Tailings – Itabirito, MG (Brazil) – VALE







Central Tailings – Main Equipment


- Pump station:
 - 01 storage tank with agitator- 20m diameter and 15m height;
 - 15 centrifugal slurry pumps Weir 14/12 AH";
 - 12 positive displacement seal pumps;
 - 24 pneumatically operated knife valves;
 - 24 ball valves with hydraulic actuation;
 - Electropneumatic panels;
 - Hydraulic Unit;





Central Tailings – Main Equipment

- Main pipe, length 6,55km and 22" with internal lining;
- 01 Pressure Monitoring Station (PMS 1);
- Choke Station at the end of the steel section near the final margin of the dam;
- HDPE pipe downstream of the choke station.





Central Tailings – Main Equipment

For the slurry waste pumping system to the Maravilhas III spotting, the main components are the same as those mentioned in the previous item, summarized below:

- Pump Station;
- The pipeline for waste is divided into sections:
 - From km 0,0 (Central Waste) to km 5,448 (TIE-IN) in carbon steel with an external diameter of 22" and internal polyurethane lining;
 - From km 5,448 (TIE-IN) to km 8,22 (Tank for gravity flow) in HDPE;630mm
 - From km 8,22 (Tank) to km 9,28 in HDPE 630mm;





Central Tailings - Main Equipment

- O2 Pressure Monitoring Station (PMS 01 e PMS 02);
- Terminal station LDS in km 8,0;
- 9,07 to km 9,28 with carbon steel branches and HDPE piping with manual sleeve valves for blocking and flow regulation, and ceramic restriction orifice.



Maravilhas III Water Intake System – Itabirito, MG (Brazil) – VALE








Maravilhas III – Main Equipment

- 01 Collection raft composed of:
 - 06 vertical centrifugal water pumps – KSB – B 22 B/5;
 - 02 HDPE pipes on 710mm length of 580,00m each
- 01 Carbon steel Header 24" and 18"







Maravilhas III - Main Equipment

- Pipe route:
 - Carbon steel 24" Extension 1.650,00 meters
 - HDPE 710mm Extension 972,00 meters
 - Four-function air valves Total 11 units
 - Valves:
 - PCV's (Pressure Sustaining Valve) 05 units
 - PSV's (Relief Valve) 02 units
 - Carbon steel 18" Extension 1.650,00 meters
 - HDPE 710mm Extension 972,00 meters
 - Four-function air valves Total 11 units
 - Valves:
 - PCV's (Pressure Sustaining Valve) 03 units
 - PSV's (Relief Valve) 02 units





Mineroduto III - Concentrate Pipeline - Germano, MG to Ubu, ES (Brazil) - Samarco









Mineroduto III - Main Equipment

Pump Station-EB6

- O2 Storage tank with agitators -21,5m in diameter x 17m in height
- 02 Centrifugal cargo pumps
- O6 Piston diaphragm pumps
 Pump Station EB7
- O1 Storage tank with agitators 21,5 m de diameter x 17 m high
- 02 Centrifugal cargo pumps
- 06 Piston diaphragm pumps





Mineroduto III - Main Equipment

- Valve Station- EV5 e EV6
- Orifice Station
- 13 Pressure Monitoring Station

Terminal Station

- 02 Storage tank with agitators 21,5 m diameter x 17 m Hight
- O1 Rupture disc Rupture at pressure of 86,5 kgf/cm²

Pipeline – 401,26km long, API 5L X70, nominal diameter of 20" and 22"



Thank You